



# Overview of works

## Track Renewal

### What we will be doing:

We will be carrying out follow-up work to complete the installation of new railway track carried out earlier this year.

### The equipment that will be used:

To carry out this work we will have on-track rail machines, generators, lights and small hand tools in use within the area. We expect the noise level to be moderate.

## Church Fenton Superstructure Works

### What we will be doing:

We are constructing a building for a power supply point.

### The equipment that will be used:

An excavator, small plant, and hand tools will be used for installation. We expect the noise level to be low to moderate.

## Sheet Pile Installation

### What we will be doing:

We're installing sheet piles into the ballast to support the track and stop it from moving.

### The equipment that will be used:

A road-rail vehicle will be used with an attachment to install the sheet piles along with support from rail workers using hand tools. We expect the noise level to be moderate to high.

## Sheet Pile Handrail Installation

### What we will be doing:

We are installing handrails onto the sheet pile walls to prevent falls from height.

### The equipment that will be used:

A road-rail vehicle will be used on the weekends to distribute handrails out to the required locations. Small hand tools will be used when working on days. We expect the noise level to be low to moderate.

## Installation of Location Cabinets

### What we will be doing:

We're installing cabinets for power and telecoms supplies.

### The equipment that will be used:

Materials will be transported to site using a road-rail vehicle and hand tools will be used. We expect the noise level to be low to moderate.

## Culvert Works and Overbridge Repairs

### What we will be doing:

We are strengthening existing culverts and overbridges. When works are being carried out to the overbridge overnight on 3–4 December, traffic management will be in place.

### The equipment that will be used:

An excavator/telehandler, an elevated work platform and small tools. An excavator with an attachment to install the sheet piles will also be used. We expect the noise level to be moderate to high.

## Lineside Fencing Installation

### What we will be doing:

We are installing fencing to prevent unauthorised access to the line.

### The equipment that will be used:

A road-rail vehicle will be utilised on the weekends and midweek nights to distribute the fencing out to the required locations. Small hand tools will then be used. We expect the noise level to be low to moderate.

If you have any additional questions or concerns, visit [www.networkrail.co.uk/contact](http://www.networkrail.co.uk/contact) or telephone our 24-hour National Helpline on **03457 11 41 41**.

